Your H2O Pro
P. O. Box 233
Janesville, CA 96114
(530) 253-3601
CA License #867400

Estimate

DATE	ESTIMATE NO.
5/27/2025	1373

NAME / ADDRESS	Ship To
GOLD MOUNTAIN COMMUNITY SERVICES DISTRICT P.O. BOX 5 CLIO, CA 96106	GOLD MOUNTAIN COMMUNITY SERVICES DISTRICT WELL #8

QTY	DESCRIPTION	EACH	TOTAL
	THE FOLLOWING RECOMMENDATION IS BASED ON THE CLIENT SUPPLIED INFORMATION FURNISHED. SHOULD THE WATER CHARACTERISTICS CHANGE IN THE FUTURE, A NEW ANALYSIS AND EQUIPMENT REVISIONS/ADDITIONS MAY BECOME NECESSARY.		
	FILTRATION SYSTEM		
1	TO FURNISH THE LABOR, MATERIAL, & EQUIPMENT NECESSARY FOR THE INSTALLATION OF TWO NEW 21X62 TURBIDEX FILTERS WITH MAV VALVE. INCLUDES THE INSTALLATION OF DRAIN LINE OUT THE EXTERIOR WALL WHICH WILL FLUSH OPEN DISCHARGE ON TO THE GROUND SURFACE BELOW DURING BACKWASH CYCLES. THIS SYSTEM IS SIZED FOR HIGH FLOW USING A SECOND WATER SOURCE WITHIN THE EXISTING PUMP HOUSE TO BACKWASH FILTERS UTILIZING THE MAV VALVES AND A PROFESSIONAL SERVICE RECOMMENDED ANNUALLY.	13,822.00	13,822.00
	MATERIALS:		
	2) 21X62 TURBIDEX FILTERS MISC. PLUMBING/ELECTRICAL		
	NOTE: THIS ESTIMATE INCLUDES AN AVERAGE DRAIN LINE PLACEMENT THROUGH THE CLOSEST EXTERIOR WALL FLUSHING ON TO THE GROUND SURFACE BELOW. ANY BELOW GROUND DRAIN LINE CONNECTION OR EXTENSION IS EXCLUDED FROM THIS ESTIMATE.		

THANK YOU FOR THIS OPPORTUNITY TO SUBMIT AN ESTIMATE FOR YOUR CONSIDERATION!! VALID FOR 30 DAYS.

Subtotal	
Sales Tax (0.0%)	
TOTAL	

Phone #	Fax #	E-mail
(530) 253-3601	(530) 253-2881	KERRI@YOURH2OPRO.COM